City Council Introduction: **Monday**, June 4, 2001 Public Hearing: **Monday**, June 11, 2001, at **1:30** p.m.

FACTSHEET

TITLE: SPECIAL PERMIT NO. 1901, VAVIK RIDGE COMMUNITY UNIT PLAN, requested by Brian D. Carstens and Associates, for 22 dwelling units of elderly housing, including 100 percent density bonus, with requests to waive sidewalk design standards; front, rear and side yard setbacks; and the 3-to-1 depth-to-width ratio, on property generally located at South 56th Street and Elkcrest Dr.

STAFF RECOMMENDATION: Conditional Approval.

ASSOCIATED REQUEST: Preliminary Plat No. 01001,

Vavik Ridge (01R-140)

SPONSOR: Planning Department

BOARD/COMMITTEE: Planning Commission

Public Hearing: 05/16/01 Administrative Action: 05/16/01

RECOMMENDATION: Conditional Approval (9-0: Schwinn, Taylor, Hunter, Steward, Newman, Duvall, Krieser, Carlson and Bayer voting 'yes').

Bill No. 01R-139

FINDINGS OF FACT:

- 1. This community unit plan and the associated preliminary plat were heard at the same time before the Planning Commission.
- 2. The Planning staff recommendation of conditional approval is based upon the "Analysis" as set forth on p.3-4.
- 3. The applicant's testimony is found on p.7.
- 4. There was no testimony in opposition.
- 5. The Planning Commission agreed with the staff recommendation.
- 6. The Site Specific conditions of approval required to be completed prior to scheduling this application on the Council agenda have been submitted by the applicant and approved by the reviewing departments.

FACTSHEET PREPARED BY: Jean L. Walker	<u>DATE</u> : May 21, 2001
REVIEWED BY:	DATE : May 21, 2001

REFERENCE NUMBER: FS\CC\FSSP1901

LINCOLN CITY/LANCASTER COUNTY PLANNING STAFF REPORT

P.A.S.#: Preliminary Plat No. 01001 Date: May 7, 2001

Special Permit No. 1901

Vavik Ridge CUP

Note: This is a combined staff report for related items. This report contains a single background and analysis section for all items. However, there are separate conditions provided for each individual application.

PROPOSAL: Brian Carstens, on behalf of Michael Thomalla and Arty Fortney, is proposing a Preliminary Plat of 11 lots and 1 outlot with waivers to the sidewalk design standards, front, rear, and side yard setbacks, and the 3 to 1 depth to width ratio, and a Special Permit for Community Unit Plan and elderly housing.

GENERAL INFORMATION:

APPLICANT: Michael Thomalla and Arty Fortney

Woods Bros. Realty 7100 S. 29th Street Lincoln, NE 68516

CONTACT: Brian Carstens

Brian Carstens and Associates 2935 Pine Lake Road, Suite H

Lincoln, NE 68516

LAND OWNER: Richard L. Svoboda, Michael L Thomalla, Adrian Meuse-Thomalla

Douglas D. Schmidt, and Nicole L. Schmidt

631 Sycamore Dr. Lincoln, NE 68510

LOCATION: S. 56th Street and Elkcrest Dr.

LEGAL DESCRIPTION: Lot 126 I.T. in the NE quarter of Section 8, T9N, R7E of the 6th P. M., Lincoln, Lancaster County, Nebraska.

EXISTING ZONING: R-1 Residential

SIZE: Approximately 2.73 Acres

EXISTING LAND USE: Mobile home court

SURROUNDING LAND USE AND ZONING: Surrounded with single family dwellings zoned R-1 on all four directions.

COMPREHENSIVE PLAN SPECIFICATIONS: Designated as Urban Residential in the 1994 Lincoln/Lancaster County Comprehensive Plan. The fifth goal of Future Urban Residential Needs and Plan on page 44 of the Comprehensive Plan states:

Encourage the development of housing that is appropriate to the requirements of households with special needs, including but not limited to, the elderly, the physically and/or mentally challenged, and households in crisis.

HISTORY: Changed from A-1 Residential to R-1 Residential during the 1979 Zoning Update.

SPECIFIC INFORMATION:

UTILITIES: The proposed methods of providing utilities and services are satisfactory.

TOPOGRAPHY: The site gently slopes from the north to south.

TRAFFIC ANALYSIS: S. 56th Street provides access to the proposed site. S. 56th Street from Van Dorn Street to Pioneers Blvd. is classified as a principal arterial in the Comprehensive Plan. Due to the low volume of traffic from the proposed subdivision, Public Works Department is not requesting a turn lane on S. 56th at Vavik Place.

PUBLIC SERVICES: Larson Park is located to the southwest of the proposed site. The closest fire station is located at 48th and Claire Ave.

ALTERNATIVE USES: The existing mobile home court.

ANALYSIS:

- 1. This application includes a preliminary plat of 11 duplex lots and a special permit for Community Unit Plan with 22 units of elderly housing.
- 2. The density calculation indicates that the proposed site permits a maximum of 11 dwelling units.
- 3. The applicant is requesting 100 percent density bonus under the provision of Section 27.63.210(h)(3) in the Lincoln Zoning Ordinance, which states that up to 100 percent of the dwelling units may be permitted, provided that all elderly and retirement housing, related facilities, and the bonus units comply with Sections 2.1 (General Standards) and 2.2 (Individual Unit Design Standards) of Chapter 3.40, Design Standards for Density Bonuses as adopted by the City Council.
- 4. Section 27.63.210, Permitted Special Use: Elderly or Retirement Housing states:

The height and yard requirements of the district in which the proposed use is located may be adjusted to provide flexibility in the placement of buildings and to provide compatibility with surrounding uses except that solar access to adjacent buildings or buildings on lands under other ownership shall not be reduced by such adjustment.

5. The applicant is requesting modifications of Section 27.11.080(a) of the zoning Ordinance, the front, rear, and side yard setback requirements.

- 6. The applicant is requesting a waiver of Section 26.23.140(a) of the Subdivision Ordinance to allow Lots 1 through 8, Block 1, Lots 1 through 4, Block 2, and Lots 1 through 10, Block 3 to exceed the maximum 3 to 1 depth to width ratio requirement, and the sidewalk design standards. The lots as proposed have a depth to width ratio of approximately 4 to 1.
- 7. A modification of Section 26.23.095 of the Subdivision Ordinance was requested to waive sidewalks along the east side of S. 55th Court, and the south side of Vavik Place. However, to receive the 100 percent density bonus, sidewalks should be installed on both sides of streets to provide pedestrian circulation.
- 8. The applicant's response is to provide sidewalks along both sides of S. 55th Court and Vavik Place, with a waiver of the 4' requirement between the sidewalk and the back of the curb on both sides of S. 55th Court. The applicant indicated that the snow would be removed from the sidewalks and driveways at the same time the roadways are plowed. Considering the use of S. 55th Court and the traffic volume within the subdivision, this design will better suit the needs of the residents.
- 9. The Public Works and Utilities Department has no objection to the application and the requested waivers and modifications.
- 10. The Erosion and Sediment Control Plan must address the comments from the Lower Platte South Natural Resources District.

STAFF RECOMMENDATION:

Preliminary Plat No. 01001 Special Permit No. 1901 Conditional Approval Conditional Approval

Approval of modification of required front yard from 30' to 25' along S. 56th Street frontage, from 30' to 26' along the north side of Vavik Place and the east and west side of S. 55th Court.

Approval of modification of required side yard from 20' to 5' on all lots.

Approval of modification of required rear yard from 20 percent of lot depth to 12' on Lots 1 through 8, Block 1, and to 20' on Lots 1 through 4, Block 2, and Lots 1 through 10, Block 3.

Approval of modification of the 3 to 1 depth to width ratio on Lots 1 through 8, Block 1, Lots 1 through 4, Block 2, and Lots 1 through 10, Block 3.

Approval of waiver of sidewalks along the east side of S. 55th Court south of Vavik Place.

Approval of modification of sidewalk design standard of 4' between the sidewalk and the curb to 0' along both sides of S. 55th Court.

CONDITIONS FOR SPECIAL PERMIT NO. 1901

Site Specific:

- 1. After the applicant completes the following instructions and submits the documents and plans to the Planning Department office and the plans are found to be acceptable, the application will be scheduled on the City Council's agenda:
 - 1.1 Revise the site plan to show:
 - 1.1.1 Note 15 from the site plan adjusted as per Planning Commission approval.
 - 1.1.2 Additional note on the site plan stating that the 3 parking stalls shall be screen at the request of the property owner of Lot 3, Block 1.
 - 1.1.3 Additional note on the site plan stating that decks shall be prohibited on the rear of the units on Lots 3, 4, 5, Block 1.
 - 1.1.4 Sheet 1 of 5 instead of 1 of 6.
 - 1.1.5 Street trees on the private streets planted at least 5' from the back of the sidewalk.
 - 1.1.6 Additional note on the landscape plan stating, "the street trees on S. 56th Street shall be planted on private property."
- 2. This approval permits a Community Unit Plan with 22 dwelling units of elderly housing including 100 percent density bonus provided that the City Council also approves:
 - 2.1 Preliminary Plat No. 01001
 - 2.2 A modification of required front yard from 30' to 25' along S. 56th Street frontage, from 30' to 26' along the north side of Vavik Place and the east and west side of S. 55th Court.
 - 2.3 A modification of required side yard from 20' to 5' on all lots.
 - A modification on required rear yard from 20 percent of lot depth to 12' on Lots 1 through 8, Block 1, and to 20' on Lots 1 through 4, Block 2, and Lots 1 through 10, Block 3.
 - 2.5 A modification on the 3 to 1 depth to width ratio on Lots 1 through 8, Block 1, Lots 1 through 4, Block 2, and Lots 1 through 10, Block 3.
 - 2.6 A waiver of sidewalks along the east side of S. 55th Court south of Vavik Place.
 - 2.7 A modification of sidewalk design standard of 4' between the sidewalk and the curb to 0' along both sides of S. 55th Court.

General:

- 3. Before receiving building permits:
 - 3.1 The permittee shall have submitted a revised and reproducible final plan including 5 copies to the Planning Department.
 - 3.2 The construction plans shall comply with the approved plans.

- 3.3 Final Plats shall be approved by the City.
- 4. During the construction process, the land owner(s) will be responsible for controlling off-site dust emissions in accordance with Lincoln-Lancaster County Air Pollution Regulations and Standards Article 2 Section 32. Dust Control measures shall include, but not limited to application of water to roads, driveways, parking lots on site, site frontage and any adjacent business or residential frontage. Planting and maintenance of vegetable ground cover will also be incorporated as necessary.

STANDARD CONDITIONS:

- 5. The following conditions are applicable to all requests:
 - 5.1 Before occupying the dwelling units all development and construction shall have been completed in compliance with the approved plans.
 - 5.2 All privately-owned improvements shall be permanently maintained by the owner or an appropriately established homeowners association approved by the City Attorney.
 - 5.3 The site plan accompanying this permit shall be the basis for all interpretations of setbacks, yards, locations of buildings, location of parking and circulation elements, and similar matters.
 - 5.4 This resolution's terms, conditions, and requirements bind and obligate the permittee, its successors and assigns.
 - 5.5 The City Clerk shall file a copy of the resolution approving the permit and the letter of acceptance with the Register of Deeds. The Permittee shall pay the recording fee in advance.

Prepared by:

Ching-Yun Liang Planner

SPECIAL PERMIT NO. 1901 VAVIK RIDGE COMMUNITY UNIT PLAN and PRELIMINARY PLAT NO. 01001, VAVIK RIDGE,

PUBLIC HEARING BEFORE PLANNING COMMISSION:

May 16, 2001

Members present: Schwinn, Taylor, Hunter, Steward, Newman, Duvall, Krieser, Carlson and Bayer.

<u>Planning staff recommendation</u>: Conditional Approval.

<u>Proponents</u>

1. Brian Carstens appeared on behalf of the owners and developers. This is a community unit plan and special permit for elderly retirement housing on So. 56th, the site of an existing trailer court. It had been platted with Quail Valley back in the 1970's. The proposal today is for 11 duplex-townhome type structures on a private roadway, with several waivers of the setback requirements so as not to require a change of zone.

Carstens noted that the drainage had been of concern to some of the neighbors. A swale has been created along the rear of Lots 1 through 10, going down into an existing common area with a low flow liner and detention cell draining into that low flow liner. Thus, the drainage will not go over the hill to the neighbors to the south.

Carstens agreed with all conditions of approval as set forth in the staff reports.

Carstens also advised that the developer has met with the Quail Valley Neighborhood Assn. and the most current set of plans were distributed to the neighborhood. The neighbors are excited to see the trailer court go away.

Carlson inquired about the rear yard on the west. Carstens explained that the reduction is from 30' to 20'. There is landscaping along that line.

There was no testimony in opposition.

Public hearing was closed.

SPECIAL PERMIT NO. 1901, VAVIK RIDGE COMMUNITY UNIT PLAN ADMINISTRATIVE ACTION BY PLANNING COMMISSION:

May 16, 2001

Duvall moved to approve the Planning staff recommendation of conditional approval, seconded by Hunter.


Carlson thinks this development will be much better than the 10 trailer houses that are there.

Motion for conditional approval carried 9-0: Schwinn, Taylor, Hunter, Steward, Newman, Duvall, Krieser, Carlson and Bayer voting 'yes'.

PRELIMINARY PLAT NO. 01001, VAVIK RIDGE ADMINISTRATIVE ACTION BY PLANNING COMMISSION:

May 16, 2001

Hunter moved to approved the Planning staff recommendation of conditional approval, seconded by Duvall and carried 9-0: Schwinn, Taylor, Hunter, Steward, Newman, Duvall, Krieser, Carlson and Bayer voting 'yes'.



Preliminary Plat #01001 Special Permit #1901 Vavik Ridge S. 56th & Elkcrest Dt.




Date:

Photograph Date: 1997


009

Lincoln City - Lancaster County Planning Dept.



Preliminary Plat #01001 Special Permit #1901 Vavik Ridge S. 56th & Elkcrest Dt.

Zoning:
R-1 to R-8
Residential District
AG
Agricultural Cistrict
AGR
Agricultural Residential District
R-C
Residential Convervation District
C-1
Office District
C-2
Suburban Office District
C-3
Office Park District
R-T
Residential Transition District
B-1
Local Business District
B-3
Commercial District
B-4
Lincoln Center Business District
B-5
Pignared Regional Business District
B-6
Highway Commercial District
H-1
Highway Commercial District
H-2
Highway Commercial District
H-3
Highway Commercial District
H-4
General Commercial District
H-4
General Commercial District
H-4
General Commercial District
H-1
Industrial Park District
Industrial Pa



Lincoln City - Lancaster County Planning Dept.

NOT TO SCALE

NOT TO SCALE

POINT OF PESINNING 1700

PATIO OUTLOT 'A' MIDE SIDEWALK

POINT OF PESINNING 1700

PATIO OUTLOT 'A' MIDE SIDEWALK

POINT OF PESINNING 1700

PATIO OUTLOT 'A' MIDE SIDEWALK


POINT OF PESINNING 1700

PATIO OUTLOT 'A' MIDE SIDEWALK

POINT OF PESINNING 1700

PATIO OUTLOT 'A' MIDE SIDEWALK

PATIO






BRIAN D. CARSTENS AND ASSOCIATES

LAND PLANNING RESIDENTIAL & COMMERCIAL DESIGN 2935 Pine Lake Road, Suite H Lincoln, NE 68516 Phone: 402.434.2424

February 8, 2001

Ms. Kathleen A. Sellman, AICP Director of Planning City of Lincoln/ Lancaster County 555 South 10th Street Lincoln, NE 68508



RE:

VAVIK RIDGE - SPECIAL PERMIT FOR ELDERLY OR RETIREMENT HOUSING AND ASSOCIATED PRELIMINARY PLAT

Dear Kathleen,

On behalf of the owners and Regal Building Systems, Inc., we submit the above mentioned applications for your review. Vavik Ridge is located about 1 block north of South 56th Street and Elkcrest Drive, the site of an existing trailer park. This site contains 2.73 acres and is currently zoned 'R-1'.

We are proposing to remove the 10 existing trailer homes and the existing framed house to develop a Community Unit Plan containing 11 duplex/ townhome buildings geared for the retirement or elderly housing market. Each lot will take access from a private roadway. Public water and sanitary sewer service is also proposed. We are providing a 'passive recreation area' consisting of a patio and gazebo, with a sidewalk/ walking trail through the project. This type of recreational amenity has been very appropriate considering the market we are selling too.

We are requesting a 'density bonus' of 100% as the units will comply with section 2.A and 2.B of the 'Density Standards for Density Bonuses, as adopted by the City Council. Also, we meet the other 3 criteria as follows. The site is larger than 2 acres. The site contains 2.73 acres. The project is less than 2,640 feet from a designated community or neighborhood center. Edgewood Center is less than one half mile from Vavik Ridge. The project is contiguous to a designated arterial street. South 56th Street is an arterial street.

We had previously met twice with the adjoining neighborhood last year in regards to a different proposal for the same site. On January 22, 2001 we met with the same neighborhood group and presented Vavik Ridge to them. There was overwhelming support for the project. They were excited to see the project move forward to remove the existing trailer court from the area. However, there was one individual that had concerns about traffic on South 56th Street.

We are requesting a waiver of sidewalks on the North side of Vavik Place and the East side of South 55th Court. We feel there is no need for parallel sidewalks to serve to small number of dwelling units.

We are requesting a waiver of the front yard setback from 30' to 25' along the South 56th Street frontage and from 30' to 22' along the North side of Vavik Place and the East side of South 55th Court. With the dedication of 17 feet of additional right of way, the units will still be setback farther that existing single family homes on the west side of South 56th Street. The front yard setback along the internal private roadways have no effect on adjacent property owners.

Page 2

We are requesting a waiver of the side yard setback from 10' to 5' on the internal property lines. We are also requesting a waiver of the rear yard setback from 23.6' to 20' on lots 1-10 Block 3. We are requesting a waiver of the rear yard setback from 18.4' to 12' on Lots 1-8, Block 1. We are requesting a waiver of the rear yard setback from 30' to 20' on Lots 1-4, Block 2. The above waivers are requested in lieu of submitting a change of zone from R-1 to R-2. We feel this would be a more appropriate action at this time. Some of the requested waivers are actually side yards if you look at setback requirements for the existing Lot 126 I.T. In some cases, we have almost doubled the required side yard setbacks on the north and south ends of the project.

Please contact me if you have any further questions.

Sincerely,

Brian D. Carstens


Page 2


CC.

Marty Fortney Mike Thomalla Larry Corbet

ENCLOSURES:

20 copies of sheet 1 of 5 6 copies of sheets 2 through 5 of 5 Application for a Special Permit Application for a Preliminary Plat Certificate of Ownership Application fees of \$1,135.00 8-1/2" x 11" reductions of the plans 3 copies of Preliminary Soils Analysis






BRIAN D. CARSTENS AND ASSOCIATES

LAND USE PLANNING RESIDENTIAL & COMMERCIAL DESIGN 601 Old Cheney Road, Suite C Lincoln, NE 68512 Phone: 402.434.2424

March 19, 2001

Ms. Kathleen A. Sellman, AICP Director of Planning City of Lincoln/ Lancaster County 555 South 10th Street Lincoln, NE 68508



RE: VAVIK RIDGE - PRELIMINARY PLAT NO. 01001 VAVIK RIDGE CUP & ELDERLY or RETIREMENT HOUSING - SPECIAL PERMIT NO. 1901

Dear Kathleen,

In response to the letter dated March 9, 2001we are responding to your comments.

- 1. We have had Joe Kerr the Surveyor sign the Surveyor's Certificate.
- 2. We have listed the requested waivers under the heading "Waivers" on the Site Plan.
- 3. We have listed the 3 to 1 lot dept ratio as a wavier under the wavier section on the Site Plan. The reason we have requested that wavier is because Duplex style Townhome lots are similar to various projects throughout the City of Lincoln.
- 4. We have listed the setback waivers under the wavier section on the Site Plan.
- 5. We have labeled the 5 feet side yard setback.
- 6. We have labeled the rear yard setback in Blocks 1 and 2.
- 7. We have labeled the open space as Outlot 'A'.
- We have labeled Outlot 'A' as Open Space.
- After speaking with Buff Baker of Public Works we have relocated the sidewalks on S. 55th Court to adjacent to the Private Roadway. We have now shown sidewalks on all sides of S. 55th Court and Vavik Place except adjacent to the Detention cell. We feel it is not needed because there are no homes on that side of the street.
 - 10. We have shown the sidewalks in a continuous pattern through the driveway. We have shown the northern most sidewalk connecting from the recreational area to S. 56th Street public sidewalk.
 - 11. We have revised Note 3 as requested.
 - 12. Note 7 now refers to "NAVD".

Page 2

- 13. We revised the Planning Commission Approval and Acceptance Block to include "Preliminary Plat" and eliminated "Special Permit".
- 14. We have added sheet 5A Topographic Site Plan, it shows all of the existing trees and calls out the sizes and types.
- 15. We have revised the Scotch Pines to be Colorado Spruce.
- We have added note 13

The grades have been revised so that the sanitary sewer can be run in a positive direction with the street profile.

- 17. A note has been added to state that erosion control measures will be taken. A note has also been added that the developer will be responsible for controlling off-site dust emissions in accordance with Lincoln-Lancaster County Air Pollution Regulations and Standards. See note 13 on the Site Plan.
- 19. Note 14 has been added.

The following are a list of requested waivers:

Lots 1 through 8, Block 1; Lots 1 through 4, Block 2; and Lots 1 through 10, Block 3 exceed the maximum 3 to 1 depth to width ratio as required by Section 26.23.140(a) of the Subdivision ordinance.

Front Yard setback requirements from 30 feet to 25 feet along S. 56th Street frontage.

Front yard setback requirements from 30 feet to 26 feet along the North side of Vavik place and the east and west side of South 55th Court.

Rear yard setback from 20.25, 21.35 and 19.2 feet to 12 feet on Lots 1 thru 8, Block 1.

Rear yard setback from 22.8 feet to 20 feet on Lots 1 thru 10; Block 2.


Side yard requirements of 20 feet to 5 feet on all lots.

Sidewalk waived on the East side of S. 55th Court, South of Vavik Place.

Please contact me if you have any further questions.

Sincerely,

Brian D. Carstens




Page 3

CÇ.

Marty Fortney Mike Thomalla Larry Corbet

ENCLOSURES:

16 copies of sheet 1 of 5 6 copies of sheets 2 through 5A of 5 8-1/2" x 11" reductions of the plans





BRIAN D. CARSTENS AND ASSOCIATES

LAND USE PLANNING RESIDENTIAL & COMMERCIAL DESIGN 601 Old Cheney Road, Suite C Lincoln, NE 68512 Phone: 402.434.2424

April 27, 2001

Mr. Ray F. Hill, Assistant Planning Director Planning Department City of Lincoln/ Lancaster County: 553 South 10th Street Lincoln, NE 68508

RE; VAVIK RIDGE - PRELIMINARY PLAT#01001 & SPECIAL PERMIT #1901 SOUTH 56TH STREET AND ELECTREST DRIVE

Dear Ray,

As per our meeting yesterday afternoon, we need to request an additional waiver of the Subdivision Ordinance -Design Standards. We have shown 4 foot wide sidewalks on the East and West sides of South 55th Court that are adjacent to the back of the curb along the private roadway. Design standards require a 4 foot area of gruss between the sidewalk and the curb. However, our first submittal had shown the sidewalk on the West side of South 55th Court in its standard location, but we had requested a waiver of the sidewalk on the East side of private roadway. As a compromise, we had shown the sidewalk as shown on the current plans. Therefore, the additional waiver will adjust the location of the sidewalks along South 55th Court from the standard location of 4 feet from the back of curb to 0 feet to the back of curb.

You had expressed concerns over snow removal on the sidewalks. If you refer to the plans, you will see that a vast majority of the sidewalks are included within the actual driveway approaches. The snow removal will be contracted by the homeowners association, therefore, individual homeowners will not be physically scooping the snow off the sidewalks and driveways. Also, the private roadway serves only the lots located in this development. There is no thru movement of vehicles from this site to an adjacent subdivision. Therefore, the traffic on the private roadway will be only those residents and their guests.

We are in agreement with revising general note #15 to prohibit decks on the rear of the units located on Lots 3, 5 and 5, Block 1.


We are in agreement with adding a new general note #16 to state that the owner of Lot 3, Block 1, may have the choice to screen the 3 adjacent parking stalls on Vavik Place with plant material or fencing. The owner may also choose not to screen the parking stalls on due to the topography change.

Please contact me if you have any further questions or comments.

Sincerely,

Brian D. Carstens

Marty Fortney
 Mike Thomalia



Memorandum

To: Kay Liang, Planning Department

From: Charles W. Baker, Public Works and Utilities

Subject: Vavik Ridge CUP, Special Permit # 1901, Preliminary Plat #01001

Date: April 9, 2001

cc: Roger Figard, Nicole Fleck-Toozc

The City Engineer's Office of the Department of Public Works and Utilities has reviewed the revised site plan for Vavik Ridge located on the west side of S 56th north of Elkcrest Drive with the following comments:

The relocated sidewalk on S 55th Court is satisfactory.

The continuous sidewalks through the driveways and the connection of the recreational walk to the sidewalk along S 56th Street is satisfactory.

The revised grades to show positive drainage of the sanitary sewer is satisfactory.

Public Works will not object to the requested waiver of the sidewalk on the east side of S 55th Court adjacent to the detention pond.

The calculations of the proposed detention pond have been reviewed by Lalit Jha and are satisfactory.



Memorandum

To:

Kay Liang, Planning

From:

Rachel Martin, Parks and Recreation

Date:

March 22, 2001


Re:


Vavik Ridge

Parks and Recreation Department staff have reviewed the above-referenced proposal and have the following comments:

- 1) Street trees on private streets should be planted at least 5 feet in from back of curb to avoid lifting of curb.
- 2) It should be noted on the landscape plan that the street trees on South 56th Street shall be planted on private property since South 56th is an arterial street.

Please phone me at 441-7936 with any questions.





3125 Portia St., Box 83581, Lincoln NE 68501-3581 (402) 476-2729 • FAX (402) 476-6454 www.lpsnrd.org



Memorandum

Date:

March 30, 2001

To:

Kay Liang, Planning Dept.

From:

J.B. Dixon, Stormwater Specialist, Lower Platte South Natural Resources District

Subject

Vavik Ridge CUP

I have reviewed the site plan for Vavik Ridge CUP. There are some areas that will need to be addressed on the Erosion & Sediment Control Plan.

- Slopes in and around the proposed detention cell will need to be seeded and, due to the slope, possibly protected with mulch. This includes the southwestern side of the property.
 (**temporary seeding of entire graded area is required***)
- Properly installed silt fence will be needed to protect the drainage way running adjacent to
 the western side of the property. Silt fence should be installed with no continuous runs
 longer than 100 ft, and should be designed to hold water to allow sediment to settle out of
 suspension.
- Rock rip-rap, of the proper size, may be needed at the mouth of the outlet entering the
 detention basin.

If you have any questions, feel free to call.

JBD/jb

Pc: file

Date Printed: Tuesday, February 20, 2001

IMPORTANT

Return this report with two sets of corrected plans. The corrections noted below are required to be made to the plans prior to issuance of a permit. Please indicate under each item where the correction is made by plan sheet number or plan detail number.

A seperate set of plans for review and and final approval must be submitted by the licensed installing contractor/s if fire suppression systems, sprinklers, dry powder, fire alarm systems or underground tanks are installed.

Permit # **DRF01018**

Address

Job Description: VAVIK RIDGE

Location: VAVIK RIDGE

Special Permit: Y 1901

Preliminary Plat: N

Use Permit: N

CUP/PUD: Y 01001

Requested By KAY LLANG

Status of Review: Approved

Reviewer: FIRE PREVENTION/LIFE SAFETY CODE


BOB FIEDLER

Comments:

Current Codes in Use Relating to Construction Development in the City of Lincoln:

- 1997 Uniform Building Code and Local Amendments
- 1994 Nebraska Accessibility Guidelines (Patterned after and similar to ADA guidelines)
- 1989 Fair Housing Act As Amended Effictive March 12, 1989
- 1979 Zoning Ordinance of the City of Lincoln as Amended including 1994 Parking Lot Lighting Standards
- 1992 Lincoln Plumbing Code (The Lincoln Plumbing Code contains basically the 1990 National Standard Plumbing Code and local community Amendments.)
- 1999 National Electrical Code and Local Amendments
- 1997 Uniform Mechanical Code and Local Amendments
- 1994 Lincoln Gas Code
- 1994 NFPA 101 Life Safety Code
- 1997 Uniform Fire Code and Local Amendments

Applicable NFPA National Fire Code Standards



LINCOLN-LANCASTER COUNTY HEALTH DEPARTMENT INTER-OFFICE COMMUNICATION

TO: Kay Liang DATE: 2/21/2001

DEPARTMENT: Planning

FROM: Chris Schroeder

ATTENTION:

DEPARTMENT: Health

CARBONS TO: Leon F. Vinci, MPH

SUBJECT: Vavik Ridge CUP

EH File

EH Administration

The Lincoln-Lancaster County Health Department (LLCHD) has reviewed the special permit application and has not, at this time, identified any serious negative environmental health risks. However, the following items are noted:

- Water supply will be the City of Lincoln Municipal supply.
- Sewage disposal will be the City of Lincoln Municipal Collection System.
- Means must be taken to prevent soil erosion either by wind or water. The Lower Platte South Natural Resources District should be contacted for assistance in this matter.
- During the construction process, the land owner(s) will be responsible for controlling off-site dust emissions in accordance with Lincoln-Lancaster County Air Pollution Regulations and Standards Article 2 Section 32. Dust control measures shall include, but not limited to application of water or other effective dust suppressants to roads, driveways, parking lots on site, site frontage and any adjacent business or residential frontage. Planting and maintenance of vegetable ground cover will also be incorporated as necessary.

If you have any questions, please contact me at 441-6272.

